



12394 Cannon Way
 Grass Valley, CA 95949
 (916) 585-5619
office@cprecon.com

Change Order Request #80

Date:	November 1, 2024	Contact:	Nicole Marks
Project Name:	Nepenthe Ph. 2 #1229	Company:	First Service Residential
Property Address:	316 Elmhurst	Phone Number:	(916) 929-8380
	Sacramento, CA	E-Mail:	nicole.marks@fsresidential.com
Subject:	Fence Repairs		

Scope of Work

The below scope of work is based off of visual inspection at locations provided by FSR, any scope not listed is excluded from this bid:

316 Elmhurst Fencing

Demo existing fence and railing (55 LF)	
Primer paint all new fence components using a tinted primer (660 SF)	
Re-use existing 3 inch round metal posts (11 EA)	
Install new postmaster metal post (EA)	
Install new 4x4 PT wood post (EA)	
Install new 2x4 pressure treated fence rails (165 LF)	
Install new 1x4 redwood fence boards (per LF fence) (55 LF)	
Install new 2x6 pressure treated kick board (55 LF)	
Install new 2x8 redwood cap (LF)	
Replace existing gate, re-use existing metal frame and hardware (2 EA)	
Finish paint all new fencing, both sides (SF)	
Sub-Total 316 Elmhurst Fencing	\$ (7,671.72)
Sub-Total 316 Elmhurst Fencing	\$ 5,801.91

TOTAL COST	\$ (1,869.81)
-------------------	----------------------

Project Clarifications

- Hidden damages are excluded from this proposal
- Material costs are subject to change based on pricing at the time of purchase
- Abatement or testing, such as but not limited to lead, asbestos, and organic growth is excluded
- We shall use proper care and caution to minimize damages to existing landscaping adjacent to the work area. The owner understands that some landscape damage may occur, as this is inherent to this type of work.
- Engineering, plans, permits, processing and building code upgrades are not included in this bid but are a reimburseable cost, if necessary
- All trellis and plants growing on or attached to fence, must be removed by others before work commences.
- Permit fees are excluded and are a re-imburseable cost, including acquisition time which will be charged at current T&M rates
- All materials will be primed prior to installation, to insure full coverage between two nailed wood components. Fence, such as nail heads, will be touched up after fence installation.
- Fence boards will be delivered 1-2 weeks prior to installation to allow wet materials to cure to prevent shrinkage and allow the primer and paint to adhere properly.
- Gate replacement and repairs include new, wood framing, fence boards, kick board, new latch hardware and new hinges. Existing metal frame and deadbolts will be re-used, unless otherwise specified.
- Permit acquisition will require environmental testing and the results will need to be approved by Sacramento Air Quality District prior to applying for a permit, this cost is excluded

Estimator Name: Bill Shewman

Estimator Signature: Bill Shewman

Date: 11/1/2024

Owner Name: Courtenay Delfin Brian Coates

Owner Signature:  Brian Coates

Date: 11/1/2024

Total Value Change Order Request	\$	(1,869.81)
#80		